

**NOTE TO THE SPECIFYING ARCHITECT REGARDING SECTION 11069  
STAGE EQUIPMENT SPECIFICATIONS (DRAPERY REPLACEMENT)**

This specification simply calls for replacement of stage drapery listed and the installation of the new stage drapery to the existing hardware. A drawing is not needed.

The list of drapery should be consistent with the items on the stage. Drapery items can be listed in the same order as on the stage or grouped (for example, "3 pairs of pivoting leg curtains" and "3 ceiling borders".)

Telephone 1-800-548-8982 for clarification or explanation; no charge, of course.

**SECTION 11069**  
**STAGE EQUIPMENT SPECIFICATIONS (DRAPERY REPLACEMENT)**

Part 1- General

- 1.01 This contractor shall furnish all labor, material, services, and equipment required to perform the stage equipment installation in accordance with these specifications and as necessary to complete the project.
- 1.02 Stage equipment supplier must visit the school to make a complete field check of the site conditions for the purpose of taking measurements. school personnel shall not be held responsible for accuracy. Miscellaneous items necessary for a proper installation of the stage curtains and equipment shall be supplied and correctly installed by this contractor at no additional charge to school authorities. This contractor shall be held responsible for the quality of materials and labor to insure the proper installation of the specified materials.
- 1.03 All fabrics shall be either inherently flame resistant or shall be flame-proofed by vat immersion process in accordance with standard industry practice and the requirements of the fire codes and regulations of the state, local and national authorities. Documentary evidence of compliance with Bulletin 701 of the National Fire Prevention Association will be presented before the work is considered completed.

Part 2- Materials

- 2.01 All materials shall be first quality. All curtains shall be fabricated of standard width in full length. No horizontal splicing will be allowed.
- 2.02 Materials that may be specified hereinafter are defined below with the name of the manufacturer or supplier, his trade name, and descriptive information to establish a standard for the specification. Proposed substitutes must be similar, equal in quality, and approved by the owner.
- 2.03 Valance front stage curtain shall be manufactured from 26 ½ ounce velour, Masking curtains including travelers shall be manufactured from 21 ounce velour. Sky drop shall be manufactured from seamless muslin, dyed light blue, and scrim drop shall be manufactured from seamless sharkstooth fabric.

Part 3- Execution

- 3.01 The tops of all fabric items shall be bound with 3 ½-inch jute webbing. Fullness shall be added by box pleating to the webbing, with pleats of equal size, located on each vertical seam and at intervals between the seams not to exceed 12-inches. Brass grommets, number 3, shall be centered on each box pleat. Curtains shall contain 50-percent added pleated fullness. The curtains shall be fabricated in sections lapping 24-inches for convenient points of entry. At centerline of bi-parting tracks. The lap shall be 36-inches. Hem all curtain sections to accord with standard industry practice.
- 3.02 Items to be replaced:  
All drapery being supplied shall be manufactured to the same dimensions and the same fullness as the existing drapery, using fabrics specified earlier. This contractor is responsible for accurate measurements to assure proper fit to existing hardware. Floor length drapery shall clear the floor 1 inch after installation to the hardware.

<b><u>Items to be replaced</u></b>	<b><u>Quantity of sections</u></b>	<b><u>Width at top after pleating</u></b>	<b><u>Finished Height</u></b>
------------------------------------	------------------------------------	---	-------------------------------

This contractor shall furnish extra carriers as required including reinstallation of rope on the traveler curtains and all other hardware required to complete the installations. Track and hardware will be raised and leveled to accommodate the new drapery. Final installation shall be ready for use.

- 3.03 Furnish new S-hooks and new tielines and replace broken or missing track carriers. Replace handlines on existing tracks if existing ropes are inoperative or show significant damage.
- 3.04 All stage drapery that is replaced shall be installed to existing hardware and shall be trimmed, leveled and left ready for use.

**END OF SECTION**

11069-2

**11/02/04**